

DRAFT TENDER SCHEDULE


Issued to:

Original / Duplicate

Name of work: Improvements to drains and culverts at Kodigehall Ward no 08

Sl. No.	Quantity	Description	Unit	Rates	
				In Figures	In Words
1	768.29	KSRB 3100-1: Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. NORTH Chapter 3 (P.No.142, ENo.191 of PW, P&I WTD SR 2016-17)	cum	186.92	Rupees One Hundred Eighty Six and Ninety Two Paise Only
2	125.57	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted in foundation including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications. Specification No. KBS 4-1.4.2 (P.No.12, ENo.4.2 of PW,P&I WTD S.R 2016-17)	cum	5348.76	Rupees Five Thousand Three Hundred Forty Eight and Seventy Six Paise Only
3	47.52	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortar 1:6, going flatterered, dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. Specification No. KBS 5.1.13 (P.No.23, ENo.5.6 of PW, P&I WTD S.R 2016-17)	cum	4135.22	Rupees Four Thousand Four Hundred Thirty Eight and Twenty Two Paise Only
4	79.20	KSRB (5.1.1) Providing flush pointing to square, ribbed, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after taking form to depth of 20mm flush using, including cost of materials, labour, curing complete as per specifications. (P.No.113, ENo.15.1 of PW, P&I WTD S.R 2016-17)	Sqm	102.82	Rupees One Hundred Two and Eighty Two Paise Only
5	18.46	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted in foundation and plinth including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications. Specification No. KBS 4-1.4.2 (P.No.12, ENo.4.6 of PW,P&I WTD S.R 2016-17)	cum	3767.46	Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only
6	217.37	Providing laying plain reinforced cement concrete for Box Drain walls of thickness 15cm to 20 cm including centering, shuttering, form work etc. complete as per approved drawing and design NORTH Specification No. 1500,1700,2200 PCC M 20 Grade upto 0.75 m height using concrete mixture (P.No. 265, ENo.37.9.2 of PW, P&I WTD SR 2016-17)	cum	11032.48	Rupees Eleven Thousand Thirty Two and Forty Eight Paise Only

	Description	Unit	Rates	
			In Figures	In Words
7	11.96 KSKR-4.9.2: Providing (M) 25mm reinforcement (Fe542) for RCC work including straightening, cutting, bending, hooking, pulling in position, lapping and / or welding, wherever required, tying with binding wire and anchoring in the adjoining members wherever necessary, complete as per design (bars, hooks and wastage shall not be measured and paid), cost of materials, labour, HOM of machinery complete as per specification, Specification No. KRS-4.6.3 (P.No.17, L.No.4.46.2 of PW, R&I/WD SR 2016-17)	Tonne	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three and Forty Two Paise Only
8	595.95 Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite (Jt) 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc., complete and as per drawing and the directions of Engineer in-charge, (Data Rate)	Sqm	1834.00	Rupees One Thousand Eight Hundred Thirty Four Only
9	89.10 Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite (Jt) 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc., complete and as per drawing and the directions of Engineer in-charge, (Data Rate)	Sqm	3431.00	Rupees Five Thousand One Hundred Eleven Only


 Executive Engineer
 Byatarayanapura Division
 BBMP, Bangalore - 52

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer ITB Clause T.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))